

## WORK ORDER

MASPL						
<b>Name:</b> : EASTERN ENTERPRISE, 480/B,HASHIMI ESTATE BALESHWAR.PALS ANA,SURAT-39431 7  <b>Billing Address:</b> : 480/B,HASHIMI ESTATE BALESHWAR.PALS ANA,SURAT-39431 7  <b>Shipping Address:</b> : 480/B,HASHIMI ESTATE BALESHWAR.PALS ANA,SURAT-39431 7			<b>P.O No.</b> : 202 <b>Date</b> : 30/06/2021		<b>W.O No.</b> : WO-2122-JUN-120 <b>Date</b> : 30/06/2021	
Sr.No	Item Description	Qty	Module Details / Rate	Discount	GST	Total
1	<b>RTD (PT-100) SENSOR</b> Part No:APWD-10*300 MM RTD SENSOR TYPE: PT-100 MAKE: AAVAD MODEL : APWD CONFIGURATION: DUPLEX NO. OF WIRE IN SIMPLEX:3 TOTAL NO.OF WIRES: 3+3 ACCURACY : CLASS A TEMPERATURE RANGE : -50 TO 400 DEGREE C MATERIAL OF CONSTRUCTION : SS 316 INSULATION : COMPACTED MGO INSULATION PROCESS CONNECTION: NPT PROCESS CONNECTION SIZE : 1/2 " (M) NPT FIX ( AS PER SAMPLE BELOW HEAD 130 MM) PROTECTION HEAD: DIE-CAST ALUMINUM HEAD WITH THREADED CAP & CHAIN HEAD PROTECTION CLASS :IP-65 HEAD CABLE ENTRY CONNECTION : ¾ "ET NO. OF CABLE ENTRY : SINGLE TERMINAL BLOCK : NICKEL PLATED CERAMIC TERMINAL BLOCK OD: 10 MM BELOW HEAD LENGTH: 300 MM	5	1,200	0	18	7,080
	<b>P &amp; F</b>		0		0	0
	<b>Freight</b>		0		0	0
				<b>Total:</b>		<b>7080</b>

	Seven Thousand Eighty Rupees Only		Grand Total:	7080
Delivery Time / Date :		Delivery by :		
		Courier Name :		Docket No. :
Prepared by : MANISHPRAJAPATI		Tested by : MANISHPRAJAPATI		Remarks : DELIVERY : 2 WEEK

NG

PS

Account

Store

Production